BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No. RRND/EE/Tend/16/2020-21, Date: 24.02.2021

Indent No: BBMP/2020-21/RD/WORK_INDENT47121

SCHEDULE -B

Name of Work: Removal of Debries, Berm Cuttings, Filling of Road Cutting and other road maintenance works in ward no 16 Jalahalli

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	500.00	Providing Tipper daily rate basis to the required place as per direction of the Engineer-in-charge	Nos	1790.00	Rupees One Thousand Seven Hundred Ninety Only
2	100.00	Providing J.C.B excavator on daily rate basis to the required place as per direction of the Engineer-in-charge	Nos	5968.00	Rupees Five Thousand Nine Hundred Sixty Eight Only
3	1000.00	Suply of Heavy Mazdoore On daily wage basis to therequired place as per direction of the Engineer-in-charge	Nos	468.00	Rupees Four Hundred Sixty Eight Only
4	12025.00	Patching of deep potholes by restoring the granular base course using material confirming to WBM garde - III standards /WMM wherver necessary by manual means including trimming the pothole to the required shape and size, cleaning the pothole applying tack coat at 4 kg/10sqm over the WBM/ WMM surface including cleaning etc, and covering the surface with premixed mix seal TYPE-A 20mm thick including lead, loading unloading, rolling and finishing etc., including cost of materials, labour, HOM complete as per specifications. Complete as per standard specification. 35.13.1 - do - upto 75 mm thick Pg No-260 Issue Rate From 1/01/2021	Sqm	358.00	Rupees Three Hundred Fifty Eight Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP